



**GENERAL NOTES:**

1. OVER-EXCAVATE WHERE REQUIRED TO ENSURE BOTTOM OF EXCAVATION IS A MIN. 2-FT INTO GRAVELLY SOIL.
2. CATCH BASINS (STD-614) PIPED TO DRY WELLS ARE ENCOURAGED AS A PRE-TREATMENT METHOD OR TO AVOID UTILITY CONFLICTS.
3. NO GRADE RING TO BE OFFSET MORE THAN 2" AND TOTAL OFFSET NOT TO EXCEED WALL THICKNESS OF CONE.
4. GRADE RINGS SHALL BE 2" THICKNESS MINIMUM.
5. NO WEDGES ALLOWED BETWEEN GRADE RINGS AND FRAME MUST BE SET FLUSH WITH TOP GRADE RING.

December 2021



Engineering Division

**Standard 8' Precast Dry Well**

*AS*

Approved By  
Utility Engineer  
Andy Schultz, PE

Adopted: 09/28/2020  
Revised: 04/16/2021

**STD - 616**