



GENERAL NOTES:

1. 12" OF SUB-BASE SHALL BE REMOVED AND REPLACED WITH 12" APPROVED SUB-BASE MATERIAL REMOVAL OF DELETERIOUS MATERIAL BELOW THE 12" WILL BE AT THE DISCRETION OF THE CITY ENGINEER

SPECIFICATIONS

1. ALL MATERIALS SHALL MEET CITY OF MISSOULA SPECIFICATIONS. 564 LBS OF PORTLAND CEMENT PER CUBIC YARD OF CONCRETE SHALL BE USED.
2. OTHER APPLICABLE STANDARD DRAWING
 - A. NO. 740 - TYPE "L" CURB AND GUTTER
 - B. NO. 753 - TYPICAL SIDEWALK FOR DOWNTOWN
 - C. CONSTRUCTION TRAFFIC CONTROL PLANS

December 2021



Engineering Division

Typical Sidewalk Specifications Central Business District

Approved By
City Engineer
Kevin J. Slovarp

Adopted: 08/1989
Revised: 04/03/2017

STD - 754