

MEMO – ADDENDUM #2

SPORT COURT RECONSTRUCTION

Optional Prebid Meeting | January 30, 2023 at 10 AM | 100 Hickory Street 59801

CITY OF MISSOULA PARKS AND RECREATION DEPARTMENT

To: Missoula Plans Exchange
City of Missoula Bids, RFPs & RFQs Website
Prospective Bidders on file

From: Garrick Swanson
City of Missoula Parks and Recreation
100 Hickory Street, Missoula, MT 59801

CC: Marty Rehbein
Nathan McLeod

Date: Wednesday, February 01, 2023

Subject: **Sport Court Reconstruction Optional Prebid Meeting**

Contractors attendance: Jackson Contractor Group, Knife River and Fencecrafters

- Contractor will be responsible to secure construction staking services for all project sites. 00700 General Conditions 7.2.02.B
- Owner will secure and pay for material testing
- Site restoration is not included in scope of work.
- Temporary construction fence is to remain in place through site restoration.

Questions & Answers

- **What is “Surface Protection and Repairs”?**
 - This is protection of existing curb and sidewalk for temporary access to the project site.
- Skyview Park is a bid alt. Award of Skyview Park is pending project cost for Franklin Park and Marilyn Park. All three project sites will be considered when reviewing received bids.

Sport Court at Franklin Park

- Remove and dispose of 4' chainlink fence ~ 180 LF to the pedestrian opening to the northeast. Field verify with project manager.
- Site access will be from South 10th Street West and via the existing aggregate path. Contractor will need to protect curb and sidewalk in place. The bridge from South 9th Street West to the park is for pedestrian use only, not to be used for temporary construction access. Trail surface restoration will be included in site restoration work.
- Pedestrian trail can be closed during construction activity from the bridge south to 10th Street. Pedestrian trail needs to remain open between bridge and Kemp Street.
- Project manager will coordinate services to ensure trees overhanging the path/temporary construction access are limbed up to a 12' height prior to work commencing.
- Stockpile topsoil onsite for site restoration.

Sport Court at Marilyn Park

- Site access will be from Linda Vista Blvd. Contractor will need to protect curb and sidewalk in place.
- Existing basketball court surface is to remain in place. Basketball stations are to be cut flush with existing asphalt, sharp edges removed and filled with concrete.
- Highlighted that the chain link fence footings and tennis net sleeves + center anchor footings are to be pre-dug, backfilled and compacted as per drawings prior to paving.

Sport Court at Skyview Park

- Skyview Park is a bid alt. Award of work at Skyview Park is pending project cost for Franklin Park and Marilyn Park. All three project sites will be considered when reviewing received bids.